



NATIONAL INNOVATION AND CREATIVE ECONOMY EXPO 2017 (NICE' 17) TECHPITCH

- HC PRECAST WALL PANEL -

13th OCTOBER 2017



HC PRECAST SYSTEM SDN BHD
(586697-M)
FAST • FEASIBLE • FLEXIBLE

Office

No. 23B, Jalan Seri
Sarawak 20B/KS2,
Taman Seri Andalas
41200 Klang, Selangor
Darul Ehsan

+603 3325 8995



www.hcprecast.com

Factory

Lot 1, Jalan Zurah 8, Pusat
Perindustrian Zurah
Mukim Rasa, Daerah Hulu
Selangor 44200 Rasa,
Selangor Darul Ehsan



+603 3319 8994



enquiry@hcprecast.com

CONTENT

No.	Description	Page
1	System Description	3 - 19
2	Project Using HC Precast System	20 - 27
3	Future Plan	28 - 30
4	Conclusion	31 - 34

System Description



1

SYSTEM DESCRIPTION

System Description

- Has been patented in United State (US) , Malaysia Patent (MyIPO) and Indonesian.
 - 1 US : US Patent Building Method
 - 3 MyIPO :
 1. Improvement In Building Method
 2. Panel Formwork System
 3. Earthquake Proof Wall Panel
 - 1 Indonesia Patent : Panel Dinding Yang Tahan Terhadap Gempa Bumi
- 5 patent is represent : Column , Beam and Modular Shear Keys
- 100% Malaysian invention & IBS 1 stop solution.

US Patent : Building Method


US006829870B2

(12) **United States Patent**
Hur

(10) **Patent No.:** **US 6,829,870 B2**
(45) **Date of Patent:** **Dec. 14, 2004**

(54) **BUILDING METHODS**

(75) **Inventor:** **Teow Beng Hur, Selangor Darul Ehsan (MY)**

(73) **Assignee:** **HC Precast System SDN. BHD, Selangor Darul Ehsan (MY)**

(*) **Notice:** Subject to my disclaimer, the term of this patent is extended or adjusted under 35 U.S.C. 154(b) by 16 days.

(21) **Appl. No.:** **10/285,548**
(22) **Filed:** **Nov. 1, 2002**
(65) **Prior Publication Data**
US 2004/0016199 A1 Jan. 29, 2004

(51) **Int. Cl.:** **E04C 2/38**
(52) **U.S. Cl.:** **52/656.1; 52/563; 52/631; 249/47; 249/191**
(58) **Field of Search:** **249/19, 22, 26, 249/27, 47, 191; 52/426, 562, 563, 275, 656.1, 631**

(56) **References Cited**
U.S. PATENT DOCUMENTS
2,939,500 A * 6/1960 Grant 269/102


3,288,427 A * 11/1966 Pluckebaum 249/192
5,078,360 A * 1/1992 Spota 249/26
5,102,092 A * 4/1992 Salas 249/192
5,553,430 A * 4/1996 Majumdar et al. 52/336.8
5,740,648 A * 4/1998 Piccone 52/426

* cited by examiner

Primary Examiner—Korie Chan
(74) **Attorney, Agent, or Firm—Nath & Associates PLLC; Harold L. Novick**

(57) **ABSTRACT**
A building is erected using pre-cast wall panels, preferably load-bearing wall panels having a shear key on each vertical edge and starter bars on each horizontal edge, by first erecting the wall panels, and then casting a concrete column around the vertical edges of adjacent or intersecting wall panels using movable formwork made up from a set of standard modules that can be assembled to form different configurations and sizes of column for different panel arrangements. The moulding surfaces of the modules may be shaped to provide decorative features to the columns and/or the column/wall intersections.

3 Claims, 5 Drawing Sheets



MyIPO 1/3 : Improvement In Building Method



MALAYSIA

CERTIFICATE OF GRANT OF A PATENT

In accordance with Section 31(2) of the Patents Act 1983 a patent for an invention having grant number MY - 124213 - A has been granted to HC PRECAST SYSTEM SDN BHD in respect of an invention having the following particulars :

TITLE : IMPROVEMENTS IN BUILDING METHODS.

FILING DATE : 25 JULY 2002

PRIORITY DATE : NONE

NAME OF INVENTOR : TEOW BENG HUR.

PATENT OWNER : HC PRECAST SYSTEM SDN BHD
: NO. 1, JALAN SINGA 20/E,
SEKSYEN 20,
40000 SHAH ALAM,
SELANGOR DARUL EHSAN,
MALAYSIA.

DATE OF GRANT : 30 JUNE 2006

Dated this 30 day of JUNE 2006


(MOHD. AMRAN BIN ABAS)
for Registrar of Patents
MALAYSIA

MyIPO 2/3 : Panel Formwork System



MALAYSIA

CERTIFICATE OF GRANT OF A PATENT

In accordance with Section 31 (2) of the Patents Act 1983 a patent for an invention having grant number MY - 139712 - A has been granted to HC PRECAST SYSTEM SDN. BHD. in respect of an invention having the following particulars :

TITLE : PANEL FORMWORK SYSTEM

FILING DATE : 27 MAY 2003

PRIORITY DATE : NONE

NAME OF INVENTOR : TEOW BENG HUR

PATENT OWNER : HC PRECAST SYSTEM SDN. BHD.
NO. 1, (GRD. FLOOR) JALAN SINGA 20/E
SEKSYEN 20
40000 SHAH ALAM
SELANGOR DARUL EHSAN
MALAYSIA

DATE OF GRANT : 30 OCTOBER 2009

Dated this 30 day of OCTOBER 2009


(SHAMSIAH BINTI KAMARUDDIN)
for Registrar of Patents
MALAYSIA

MyIPO 3/3 : Earthquake Proof Wall Panel



MALAYSIA

CERTIFICATE OF GRANT OF A PATENT

In accordance with Section 31 (2) of the Patents Act 1983 a patent for an invention having grant number MY-157696-A has been granted to HC PRECAST SYSTEM SDN. BHD., in respect of an invention having the following particulars :

TITLE : EARTHQUAKE PROOF WALL PANELS

FILING DATE : 22 JULY 2010

PRIORITY DATE : NONE

NAME OF INVENTOR : TEOW BENG HUR

PATENT OWNER : HC PRECAST SYSTEM SDN. BHD.
NO. 23B, JALAN SERI SARAWAK
20B/KS 2, TAMAN SRI ANDALAS
41200 KLANG
SELANGOR DARUL EHSAN
MALAYSIA

DATE OF GRANT : 15 JULY 2016

DURATION OF PATENT : 22 JULY 2010 UNTIL 22 JULY 2030

END OF PROTECTION : 14 JULY 2017 (SUBSEQUENT ANNUAL FEE SHALL FOLLOW AS STATED IN THE SCHEDULE OF FEES AT THE BACK OF THIS PAGE)

Dated this 15 day of JULY 2016


(DATO' SHAMSIAH BINTI KAMARUDDIN)
Registrar of Patents
MALAYSIA

Indonesia Patent : Panel Dinding Yang Tahan Terhadap Gempa Bumi



KEMENTERIAN HUKUM DAN HAK ASASI MANUSIA *P215760*
REPUBLIK INDONESIA *14/9 2017*
DIREKTORAT JENDERAL KEKAYAAN INTELEKTUAL
Jl. H.R. Rasuna Said Kav 8-9, Kuningan, Jakarta Selatan, 12940
Telepon: (021) 57905611 Faksimili: (021) 57905611
Laman: <http://www.dgip.go.id> Surel: dopatent@dgip.go.id

Nomor : HKI-3-HI.05.02.04.P00201000903-DP *47693*
Lampiran : 1 (satu halaman)
Hal : Pemberitahuan dapat diberi Paten

07 SEP 2017

Yth. Ir. Migni Myriasandra, S.H., M.I.P., M.SEL
PT. Oktrol International,
Kantor Taman A-9, Unit A6 & A7
Jl. Mega Kuningan, Kuningan, Jakarta 12950

Dengan ini diberitahukan, bahwa sesuai dengan hasil pemeriksaan substantif terlampir, permohonan paten berikut ini dinyatakan dapat diberi Paten:

Nomor Permohonan : P00201000903
Tanggal Penerimaan : 20 Desember 2010
Pemohon : HC PRECAST SYSTEM Sdn. Bhd
Judul invensi : PANEL DINDING YANG TAHAN TERHADAP GEMPA BUMI



00-2017-222830



Pengetik: Hendri Sinaga, M.Hum.
NIP. 196202021991031001

Tembusan:

1. Direktur Jenderal Kekayaan Intelektual (sebagai Laporan)
2. Aditia Meiriza Ashibi, ST.

Lampiran 1

HASIL PEMERIKSAAN SUBSTANTIF TAHAP AKHIR (Diberi Paten) Nomor Permohonan: P00201000903

1. Dengan ini diberitahukan bahwa:
 - a. deskripsi yang diterima adalah deskripsi:
☐ halaman asli seperti saat diajukan
☒ halaman 1-12 sesuai surat Saudara tanggal: 14 Agustus 2017
 - b. klaim yang diterima adalah klaim:
☐ nomor asli seperti saat diajukan
☒ nomor 1-5 sesuai surat Saudara tanggal: 14 Agustus 2017
 - c. gambar yang diterima adalah gambar
☐ nomor asli seperti saat diajukan
☒ nomor 1-10 sesuai surat Saudara tanggal: 14 Agustus 2017
 - d. gambar untuk publikasi B adalah: Gambar 8
2. Deskripsi dan klaim-klaim serta gambar-gambar tersebut di atas dengan ini dinyatakan telah memenuhi ketentuan Pasal 2, Pasal 3, Pasal 5, dan ketentuan lain dalam Undang-undang Republik Indonesia Nomor 14 Tahun 2001 tentang Paten, sehingga permohonan paten ini dapat dipertimbangkan untuk diberi Paten.

Aditia Meiriza Ashibi, ST.
NIP. 198105022008011021

System Description

- Register with CIDB Gred G7
- Sijil Perolehan Kerja Kerajaan
- Sijil Pengeluar IBS
- ISO 9001 : 2008

CIDB : Gred G7

278670 A

CIDB 
MALAYSIA

PERAKUAN PENDAFTARAN

Adalah dengan ini diperakui bahawa kontraktor yang dinyatakan di bawah ini telah berdaftar dengan Lembaga mengikut Bahagian VI Akta Lembaga Pembangunan Industri Pembinaan Malaysia 1994. Pendaftaran ini adalah tertakluk kepada syarat-syarat yang telah ditetapkan di belakang Perakuan ini

No Pendaftaran: 0120111104-SL137168

Nama Kontraktor: HC PRECAST SYSTEM SDN. BHD.

Alamat Berdaftar: NO.23B, JALAN SERI SARAWAK 20B/KS2
TAMAN SERI ANDALAS
41200 KLANG
SELANGOR

Gred, kategori dan pengkhususan berdaftar

G7	B	B19	B01	B04
G7	CE	CE21		

Tarikh Mula Berkuatkuasa: 08 MAR 2017

Tarikh Habis Tempoh Perakuan: 07 MAR 2019*

*Perakuan ini hendaklah diperbaharui sebelum tempohnya 60 hari sebelum tarikh habis tempoh.

STATUS: AKTIF - Kontraktor yang diawardkan projek semasa perakuan pendaftaran ini dikeluarkan.



()
b.p. Ketua Eksekutif
Bertarikh: 08 MAR 2017

CIDB : Sijil Perolehan Kerja Kerajaan

A163503

CIDB 
MALAYSIA

Sijil Perolehan Kerja Kerajaan

NO. SIJIL PENDAFTARAN
0120111104-SL137168

Adalah disahkan Syarikat/Firma seperti butir-butir berdaftar dengan Lembaga Pembangunan Industri Pembinaan Malaysia dan tertakluk kepada syarat-syarat termaktub di belakang sijil.

Tarikh Mula Berdaftar Dengan CIDB: 04/11/2011

NAMA DAN ALAMAT BERDAFTAR

HC PRECAST SYSTEM SDN. BHD.
NO.23B, JALAN SERI SARAWAK 20B/KS2
TAMAN SERI ANDALAS
41200 KLANG
SELANGOR

TEMPOH SAH LAKU:

DARI: 08/03/2017
HINGGA: 07/03/2019

GRED	KATEGORI
G7	B (Pembinaan Bangunan)
G7	CE (Pembinaan Kejuruteraan Awam)

PEGAUAI SYARIKAT YANG DITAUJIAHKAN

FADZIL BIN AHMAD
AHMAD SUHAIMI BIN ABDUL MAJID

NO. K/P

700419-02-5977
610530-03-5859



()
b.p. Ketua Eksekutif
Bertarikh: 08 MAR 2017



PENILAIAN PENGELUAR BERSTATUS IBS
ASSESSMENT OF IBS STATUS MANUFACTURER (AIS)

No. Siri: **3815**
Siri/No.






Adalah dengan ini disahkan bahawa:
It is hereby verified that:

HC PRECAST SYSTEM SDN BHD
NO 23B, JALAN SERI SARAWAK 20B/KS2
TAMAN SERI ANDALAS
41200 KLANG
SELANGOR DARUL EHSAN

Merupakan:
IS:
PENGELUAR

Lokasi Kilang:
Factory Location:
LOT 1, JALAN ZURAH 8
KAWASAN PERINDUSTRIAN ZURAH
MUKIM RASA, DAERAH HULU SELANGOR
44200 RASA
SELANGOR DARUL EHSAN

No. Laporan:
Report No.:
ASL270815IBSC0502

Tarikh Dikeluarkan:
Issue Date:
10 FEBRUARI 2017

Sah Sehingga:
Valid Until:
09 FEBRUARI 2018

Pusat IBS, CIDB Malaysia
Galeri Komponen IBS
Lot B, Jalan Chua Seng Lim
55200 Kuala Lumpur
Malaysia
TEL: 03-92816909
FAX: 03-92815820
Laman Web
ibs.cids.gov.my

Sebagai syarikat Status IBS yang mengeluarkan produk IBS berikut:
As an IBS status company that manufactures the following IBS components:

SISTEM KONKRIT PRATUANG:
- COLUMN
- BEAM
- WALL
- SLAB

Kategori: **C**


DATUK IR. ELIAS ISMAIL
 b.p Ketua Eksekutif
 CIDB Malaysia



Certificate of Registration

Certificate Number:
10898

Initial Registration Date:
25 April 2013

Re-issue Date:
20 September 2016

Expiry Date:
15 September 2018

This certificate will remain valid till expiry date subject to the company maintaining its system to the required Standard. This will be monitored regularly by ISOQAR. Further clarification regarding the scope of this certificate and the applicability of the relevant standard requirements may be obtained by consulting Alcumus ISOQAR Ltd.




Certificate No. 10898
ISO 9001

This is to certify that the Management System of

HC Precast System Sdn. Bhd.

No. 23, Jalan Seri Sarawak 20B/KS2,
Taman Seri Andalas, 41200 Klang,
Selangor Darul Ehsan, Malaysia.

has been approved by ISOQAR to

ISO 9001:2008

Scope of Activities:


Design, Outsource Manufacture and Supply of Precast Concrete Wall and Panel Formwork System


 Signed (on behalf of ISOQAR)

Issue by:
Alcumus ISOQAR LTD
Cores Court, 1 Shuibet Road, Brentford
 Middlesex TW8 9JN, U.K.
 Tel: +44 181 6000112
 www.alcumusisoqar.co.uk

System Description

- HCPS IBS flexibility to suit all architectural demands by using Modular Mould System. In the construction of a building, there are always 4 types of joint namely L-shape, T-shape, Cross shape and Straight joint.



- Provide speedier construction, cost effectiveness, high quality and easy standardization.

System Description


- HC Precast System (HCPS) Is a **system provider with manufacturing facilities** specialist in Industrialized Building System (IBS)
- Supply and Install Superstructure (Frame & Wall)

3 in 1 in Malaysia

- Load bearing wall



- Modular shear keys (wet joint)



- Box system




System Description


- 37.7 kN per key
 - Independent checker by JKR for HCPS Modular Shear Keys Wet Joint

IR Perunding PaduReka Sdn. Bhd.
Company No: 2080167
CONSULTING ENGINEERS
Head Office : No. 41A, Jalan Jejaka 2, Taman Maluri, Cheras, 56100 Kuala Lumpur. Tel No: 03-42662390, 03638337, 02638625 Fax: 03-42630900, 02675572
Johor Bahru Branch : 28-A, (1st Floor), Jalan Layang 10, Taman Peltang, 81200 Johor Bahru. Tel No: 067-2418007 Fax: 067-2418599
Email: per@padureka.com, padureka@gmail.com

**Cadangan Pembinaan Kompleks Bank Gen Biji
Benih Pertanian Di Ibu Pejabat Mardi, Serdang,
Selangor**

**Supplementary Independent Checker
Engineer's Report No. 5-1 on Shear Key
Joints For Precast R.C. Wall Panels**






Prepared By:
Perunding PaduReka Sdn. Bhd.
41A Jalan Jejaka 2
Taman Maluri
Cheras
55100 Kuala Lumpur

18 January 2010

AM 534 411 461 5100000 18 Jan 2010 3:00 PM PERUNDING MUDA ASEM/ENGR. NURUL HUDA



- Supplementary Independent Checker Engineer's Report No. 5-1 on Shear Key Joints For Precast R.C. Wall Panels

A_s is the minimum area of dowel reinforcement

of is the angle of internal friction between the faces of the joint.

tanaf is 1.7 from Table 5.3 of BS 8110 ; Part 1. However, this tanaf is best determined by tests under Research and Development if possible.

It is interesting to note that $0.6 \tan \phi \neq 1.0$ and $V \approx F_p$.

e) The total ultimate shear capacity of the shear key joint is assessed as follows :-

From (c) above, for R10 dowel, $V_c = 24.7 \text{ kN}$

From (d) above, for R10 dowel, $V_d = 13 \text{ kN}$

Total, $V_1 = 37.7$ kN per key

The number of effective keys times 37.7 kN shall determine the ultimate shear capacity of the shear key joint of a precast r.c. wall panel.

System Description

- HCPS has been collaboration with Agency CREAM, UTM, UiTM for earthquake test and with Nanyang Technological University, Singapore to published journal. International magazine in precast has been published in previous years.



UTM
UNIVERSITI TEKNOLOGI MALAYSIA




e-SEER
Engineering Seismology and
Earthquake Engineering Research





HC PRECAST SYSTEM SDN. BHD.

Earthquake Resistance System
Tested on
18 August 2011
@ Laboratory of Shake Table Testing
Faculty of Civil Engineering
Universiti Teknologi Malaysia
81310 Skudai, Johor




Earthquake Resistance Test of Scaled-Down Double Storey Building of HC PRECAST SYSTEM SDN. BHD.

Under 8 different real earthquake time histories over the world as follow:


Earthquake	Year	Scaled PGA (g)	Magnitude	Result
El-Centro, California	1940	0.96	7.1	
Tabas, Iran	1978	0.114	7.4	
Irpinia, Italy	1980	0.606	6.5	
Kobe, Japan	1995	1.035	6.9	
New Zealand	1987	0.165	5.6	
Taiwan SMART1	1983	0.117	6.8	
Duzce, Turkey	1999	0.075	7.1	
Malaysia Artificial	-	0.606	-	

The HC PRECAST SYSTEM performed extremely well throughout all the earthquake tests without any visible cracks or damages


Dr Azlan Adnan
 Professor of Structural Earthquake Engineering
 Faculty of Civil Engineering, Universiti Teknologi Malaysia

UTM

Earthquake Resistance Test of Scale-Down Double Storey Building



ELSEVIER

Case Studies in Structural Engineering

Certificate of publication for the article titled:
 "Case study of load-bearing precast wall system subject
 to low seismic intensity by linear and nonlinear analyses "

Authored by:
Patrick Liq Yee Tiong, Sing Ping Chiew and Beng Hur Teow

Published in:
Volume 6C, 2016, Pages 11-21

Nanyang Technological University, Singapore

System Description

- Ability to address challenges and resolve critical construction issues



a) No leaking

b) No crack

Training unit : - 9 years expose precast wall, precast staircase, half slab & precast beam with in-situ column.
- No Maintenance - No Touch-up - No Water proofing - No Leaking - No crack



Drawing Conversion 2D To 3D







Original 2D	To	System 3D
-------------	----	-----------


Original 2D	To	System 3D
-------------	----	-----------

Original 2D	To	System 3D
-------------	----	-----------

System Drawing - 3 D



Wet Work Joint



SYSTEM PROVIDER



HC PRECAST SYSTEM SDN. BHD. (586697-M)
No.23, Jalan Seri Sarawak 208/KS2, Taman Seri Andalas,
41200 Klang, Selangor D.E. Tel:03-3323 8995 Fax:03-3319 8994
e-mail:enquiry@hccast.com, <http://www.hccast.com>
DETAILS SHOWN IN THIS DRAWING ARE PROPERTY OF HC PRECAST SYSTEM & PROTECTED
BY PATENTS. ALL COPYRIGHT ARE RESERVED. (US 6,829,870 B2) & (MY-124213-A)

MANUFACTURER

HC MANUFACTURING SDN. BHD. (585570-T)
No.23-1, Jalan Seri Sarawak 208/KS2, Taman Seri Andalas,
41200 Klang, Selangor D.E.
Tel:03-3323 7999 Fax:03-3323 8993

DRAWN :	HC
DATE :	DEC 2015
CHECKED :	3993
DESIGNED :	3993
APPROVED :	3993
SCALE :	1:75

SINGLE STOREY BUNGALOW,
JALAN KEBUN, KLANG.
WALL HEIGHT: 3850mm
BUILT UP AREA: 2467.20 M2

DRAWING TITLE :

ARCHITECTURAL DRAWING
GROUND FLOOR COLUMN LAYOUT

DRAWING NO :	HC/SSB/K/2D-01	REV :	-
SYSTEM :	-	REV :	-

Wet Work Joint

Lowering Of Building Cost . The best way is to build faster and cheaper .

- One of the ways is by using Industrial Building Systems (IBS) .
- System Provider or Manufacturer should provide installer of the Building Precast Element .



Completed in 7 days with 6 workers :

- Precast Element	:	88 %
- Wet Work	:	12 %
Ex-Factory	:	RM 900.00 per m3
Volume	:	13.16 m3 / unit
Amount	:	RM 11,844.00 per unit
GFA	:	800 ft2
Cost	:	RM 14.805 per ft2 GFA

Note :

All works below lowest floor finish, ground floor slab & footing by other .
All walls & common party walls at 100 mm thick .



Responsibility :

- System Provider or Manufacturer should provide installer of the Building Precast Element .
- The wall is designed to provide adequate fire resistance according to demand (with minimum 2 hours as per BS8110) .

Project Using HC Precast System



2

**PROJECT USING
HC PRECAST SYSTEM**

Project Using HC Precast System

- **Sales Revenue**

Total Sales : RM219,163,983.20

Quantity :

- Single Storey : 1,163 units
- Double Storey : 451 units
- 3 Storey : 1 unit
- 3 Shop Lot : 42 units
- Total : 1,657 units

PROJECT USING HC PRECAST SYSTEM

3 Storey Shop Office, Klang



Shop Lot, Kota Putri



PROJECT USING HC PRECAST SYSTEM

Bungalow, Shah Alam



Bungalow, Jalan Kebun



PROJECT USING HC PRECAST SYSTEM

Semi-D, Shah Alam



Semi-D, Bukit Botak



PROJECT USING HC PRECAST SYSTEM

Double Storey, Shah Alam



Double Storey, Kota Putri



PROJECT USING HC PRECAST SYSTEM

Single Storey, Kota Putri



Single Storey, Bernam Jaya



PROJECT USING HC PRECAST SYSTEM

Show Unit, Rasa



Training Unit, Rasa



Future Plan



3 FUTURE PLAN

Future Plan

- **Licensing Agreement**

We are ready to engage and cooperate with all parties government and private sector

- **Royalty**

In discussion on technology transfer to China and Indonesia

- **Strategic Planning**

Setup 4 production plant to access the entire Malaysia strategically.

Existing

Rasa, Hulu Selangor (Main Plant)

Future Plan

- 1) Melaka
- 2) Pahang
- 3) Perak
- 4) Kedah

Future Plan

HCPS IBS Factory : Capacity

- Existing production : 1,800 – 2,500 units of single storey (1000 ft2) per year
- Supply & Install : RM900/m3 ex-factory



- Future development 13 acres : 2,500 to 3,500 units of single storey (1000 ft2) per year

- Existing production 8 acres : 1,800 to 2,500 units

Intervention / Facilitation Required

PROPOSE TO GOVERNMENT & PRIVATE DEVELOPER

Invite industrialized building system provider with manufacturing facility (flexibility to suit all architectural demands) to participate to built the show unit with work below and superstructure without finishing for the Government & Private Developer to identify the system in terms of green, environment, quality and speed for supply in its development.

1. Architect

- Appointed by the Government & Private Developer .
- Design of single storey bungalow of 1,000 ft2 (affordable home), up to superstructure without finishing.
- With M&E requirement.
- Wall finishing with plaster or skim coat only.
- Door and window frame opening.
- Ground floor without tiling.

2. Industrialized building system manufacturer have formed their BQ for superstructure (in terms of wall area) and to submit work program with sequence of work for record purposes.

3. Proper record by the Government & Private representative during construction, in terms of labour and machinery involved per day up to completion (superstructure only).

4. Cost Comparison for each Industrialized Building System Manufacturer by the Government & Private Developer (for superstructure only). Cost will be fixed for the selected manufacturer and supply to its development .

CONCLUSION




4

CONCLUSION

CONCLUSION

- Out flow currency
- Reduce foreign worker - 40%
- Built faster & cheaper
- Saving up to 15% - 30% (superstructure / frame & wall)
- Suite 100% architect demands
- Full responsibility of building





**Innovative
&
Revolutionary
Precast System**

THANK YOU