



Single Storey Terrace House
End Left Unit : RM 16,902.90

87% Precast Product at Factory
13% Wet work on Site (by system formwork)

Item	Description	Concrete Volume (m ³)
1)	Precast Panel (15pcs)	15.949
2)	Precast Beam (2pcs)	0.480
3)	Wet Joint (20nos)	2.352
	Total Concrete Volume	18.781

Calculation					
Item	Description	Concrete Volume (m ³)	Wall Area - 100mm thk (m ²)	Rate / m ² (RM)	Total Amount per unit (RM)
1)	Precast Panel + Precast Beam + Wet Joint	18.781	187.810	90.00	16,902.90

SYSTEM PROVIDER
HC PRECAST SYSTEM SDN. BHD. (586697-M)
 No.23B, Jalan Seri Sarawak 20B/KS2, Taman Seri Andalas,
 41200 Klang, Selangor D.E. Tel:03-3323 3993 Fax:03-3324 3993
 e-mail:enquiry@hcprecast.com, www.hcprecast.com

DETAILS SHOWN IN THIS DRAWING ARE PROPERTY OF HC PRECAST SYSTEM & PROTECTED BY PATENTS. ALL COPYRIGHT ARE RESERVED. (US 6,829,870 B2) & (MY-124213-A)

MANUFACTURER
HC MANUFACTURING SDN. BHD. (585570-T)
 No.23-1, Jalan Seri Sarawak 20B/KS2, Taman Seri Andalas,
 41200 Klang, Selangor D.E.
 Tel:03-3323 3993 Fax:03-3324 3993

DRAWN : ZUL
 DATE : AUGUST 2014
 CHECKED : LEE
 EXAM'D : MNG
 APPR'D : MNG
 SCALE : NTS

Single Storey Terrace House
End Left Unit

DRAWING TITLE : Single Storey Terrace House **10**
 DRAWING NO : HC/WP REV : -
 SYSTEM : - REV : -